

Non-Stop
SCAFFOLDING
"The Fastest Way To The Top"
 1314 Hoadley St.
 Shreveport, LA 71104
 Phone: 1-800-845-0845
 Phone: 318-222-0702
 Fax: 318-222-0707
 www.nonstopscaffolding.com

JUNIOR



Name:
 Company Name:
 Address:
 City State Zip:
 Phone:
 Fax Phone:
 Mobile Phone:

DATE: April 16, 2008

Length= 273 273 ft. actual length
Height= 24 40 legs long

- Based on the given wall length and height...
- The scaffold will be 273 feet long.
 - The towers will be a little under 22.5 feet high.
 - There will be 3 extension(s) above the base tower.
 - The masons' feet will be 19.0 feet off the ground at the very top.

NON-STOP JUNIOR SCAFFOLDING COMPONENTS

Quan.	Description	Unit Price	Ext. Price	Unit Wt.	Ext. Wt.
40	8'-8" Base Tower	188	7,520	65	2,600
40	Elevating Carriage & Winch	395	15,800	84	3,360
120	4'-6" Jr Extension	82	9,840	31	3,720
40	Jr Laborers' Bracket	93	3,720	32	1,280
100	X-Brace	21	2,100	17	1,700
19	Straight Brace	16	304	13	247
	Adjustable Straight Brace	26		15	
80	Leveling Jack	29	2,320	14	1,120
38	Guardrail Post	38	1,444	11	418
8	Guardrail End (Set of 2)	84	672	30	240
4	Inside Corner Arm	95	380	40	160
1	Swivel Forklift Bar	775	775	160	160
	Pulley Extender	36		15	
	Wall Tie-in Bracket	45		10	
	Rack Brackets (4 pcs.)	59		52	
	Rack Leveler	55		16	
	Laborer EGR	56		21	
	Masons EGR	28		9	
	Jr Winch, Cable, Pulley	265		41	
	UPGRADE - NBL LABORERS	2,000		400	
	UPGRADE - NBL MASONS	4,140		1,520	
1	Parts Basket	459	459	315	315
	Parts Basket Guardrail Kit	175		59	
	Add Item				
	Add Item				
			45,334	Total wt.	15,320 lbs.
	Plus LA Sales Tax:		45,334		
	Plus Steel Market Surcharge:		4,080		
			49,414		
	Plus freight:			(Approx.)*	
	TOTAL AMOUNT:		\$49,414		

- The pulley extender is used inside when another extension would hit the ceiling. It gives you the extra height you need to put your mason's head against the ceiling.
- Prices effective 1/1/2006
- This quote is good for 30 days.

NOTES: