

Non-Stop
SCAFFOLDING
"The fastest way to The Top"
 1314 Hoadley St.
 Shreveport, LA 71104
 Phone: 1-800-845-0845
 Phone: 318-222-0702
 Fax: 318-222-0707
 www.nonstopscaffolding.com

JUNIOR



Name:
 Company Name:
 Address:
 City State Zip:
 Phone:
 Fax Phone:
 Mobile Phone:

DATE: April 16, 2008

Length= 63 63 ft. actual length
Height= 15 10 legs long

Based on the given wall length and height...

- The scaffold will be 63 feet long.
- The towers will be a little under 13.5 feet high.
- There will be 1 extension(s) above the base tower.
- The masons' feet will be 10.0 feet off the ground at the very top.

NON-STOP JUNIOR SCAFFOLDING COMPONENTS

Quan.	Description	Unit Price	Ext. Price	Unit Wt.	Ext. Wt.
10	8'-8" Base Tower	188	1,880	65	650
10	Elevating Carriage & Winch	395	3,950	84	840
10	4'-6" Jr Extension	82	820	31	310
10	Jr Laborers' Bracket	93	930	32	320
15	X-Brace	21	315	17	255
4	Straight Brace	16	64	13	52
	Adjustable Straight Brace	26		15	
20	Leveling Jack	29	580	14	280
8	Guardrail Post	38	304	11	88
4	Guardrail End (Set of 2)	84	336	30	120
1	Inside Corner Arm	95	95	40	40
1	Swivel Forklift Bar	775	775	160	160
	Pulley Extender	36		15	
	Wall Tie-in Bracket	45		10	
	Rack Brackets (4 pcs.)	59		52	
	Rack Leveler	55		16	
	Laborer EGR	56		21	
	Masons EGR	28		9	
	Jr Winch, Cable, Pulley	265		41	
	UPGRADE - NBL LABORERS	500		100	
	UPGRADE - NBL MASONS	1,035		380	
1	Parts Basket	459	459	315	315
	Parts Basket Guardrail Kit	175		59	
	Add Item				
	Add Item				
			10,508	Total wt.	3,430 lbs.
	Plus LA Sales Tax:		10,508		
	Plus Steel Market Surcharge:		945		
			11,453		
	Plus freight:			(Approx.)*	
	TOTAL AMOUNT:		\$11,453		

- The pulley extender is used inside when another extension would hit the ceiling. It gives you the extra height you need to put your mason's head against the ceiling.
- Prices effective 1/1/2006
- This quote is good for 30 days.

NOTES: